

SCOPE OF SERVICES

Replacement Kitchen Ceiling Main Kitchen Camp David

1. BACKGROUND INFORMATION

The ceiling of the Main Kitchen at the Zijin Rosebel Gold Mines N.V. camp needs to be replaced. The replacement consists of two areas:

- A. The Dining area (approximately 775 square meters)
- B. Production area (approximately 435 square meters)

2. SCOPE OF SERVICES

2.1. Specific work

- A. Ceiling replacement of the Dining area. Remove the current ceiling tiles, installation of metal framing and place sustainable durable ceiling material. To be finished and painted in acryl latex paint. Approximate size ~775 square meters.
- B. Ceiling replacement of the Production area. Remove the current ceiling tiles, installation of metal framing and place sustainable durable ceiling material (water and heat resistant) Approximate size ~425 square meters.

2.2. Responsible department

RGM Infrastructure Department

2.3. Location

Main Kitchen located in Camp David, RGM Mine Site, Brokopondo, Suriname

2.4. Start date & period of implementation

The intended start date is 1 February 2025 and the period of implementation of the contract will be 60 days from this date (2 April 2025)

2.5. Facilities to be provided by RGM

- Accommodation, kitchen and laundry services for supplier contractors.
- New lighting for entire ceiling
- Electricians for removal old lighting, to install new electrical point and to install new lighting.

3. REQUIREMENTS

3.1. Personnel to be provided by the Contractor

Skilled and experienced construction workers, roofers, labourers. A project supervisor/General foreman.

The contractor must permanently cover the positions that are required for the proper performance of the services. For all the positions offered, there must be relief personnel who cover the positions of the holders

3.2. Facilities to be provided by the Contractor

- Ceiling materials
- Metal framing material
- All other construction and attachment materials (channels, wiring, screws etc)
- Acryl latex paint, rollers and all painting attributes
- Protective plastic covering
- Daily reporting (Gantt Chart) on progress of construction
- Health protocols: Contractors must adhere to the on-site health and safety protocols.
- Housekeeping after completion of the project
- Manhours to be submitted every month for the period 16th of the previous month – 15th of the month
- A Qualified H&S representative from the contractor
- Qualified working at height employees (with valid documentation)
- Qualified/certified PPE, tools, equipment, scaffolding etc.(to be inspected by H&S or qualified RGM representative)
- Waste management to be done according to the onsite waste management procedure.

