

Scope of Work: RGM-IS-2025-18 Camp David soccer field rehabilitation

PROJECT NO. RGM-IS-2025-18	DATE SUBMITTED
Camp David Soccer Field Rehabilitation	27/06/2025 (dd/mm/yyyy)
PROJECT OBJECTIVES	
The project involves the rehabilitation of an existing soccer field by upgrading the playing surface with synthetic grass	

### Step 1. Project Deliverables

TASK NO.	DESCRIPTION
1	Fully 8,844.56 m <sup>2</sup> rehabilitated artificial grass field artificial grass with 0-25 mm gravel running track around the field.
2	Completed drainage systems with a slope of approx. 0.5 %
3	Markings and installations meeting the drawing requirements.
4	Maintenance of the field (4 times in a year)

### Step 2. List of project Tasks

Work breakdown structure (WBS) attached	NO	X	YES
Provide link, if applicable.			

TASK NO.	DESCRIPTION	FOR DELIVERABLE NO. ... ENTER TASK #
1	a) Remove existing surface and prepare the foundation for artificial. b) Level and grade the field to ensure proper drainage. c) Install artificial grass of the field, including base preparation, infill and secure anchoring.	
2	Drainage and install an efficient drainage system to prevent waterlogging. Comply to all company environmental and industry regulations.	
3	Apply permanent markings that meet drawing.	

### Step 3. Out of Scope

This project <b>will NOT accomplish or include</b> the following:	<ul style="list-style-type: none"> <li>• Perimeter fencing of the field</li> <li>• Installation of lighting systems</li> </ul>
---	--

### Step 4. Project outcomes

NO.	OUTCOMES
1	The current field will be upgraded according to 8,844.56 m <sup>2</sup> of artificial grass and 1,164 m <sup>2</sup> of running track.
2	Field markings will be placed according to the measurements in the drawing
3	Maintenance of the field (4 times in a year)

### Step 5. Project Constraints

PROJECT START DATE	01/08/2025 (dd/mm/yyyy)
LAUNCH / GO-LIVE DATE	
PROJECT END DATE	01/10/2025 (dd/mm/yyyy)
LIST ANY HARD DEADLINE(S)	
LIST OTHER DATES / DESCRIPTIONS OF KEY MILESTONES	2 months from Start date to complete
FACILITIES TO BE PROVIDED BY RGM	<ul style="list-style-type: none"> <li>• Map of the area.</li> <li>• Fuel</li> </ul>

<b>FACILITIES TO BE PROVIDED BY CONTRACTOR</b>	<ul style="list-style-type: none"> <li>• Insurance.</li> <li>• All required material for construction.</li> <li>• All required drawings, cost breakdown and Gantt chart.</li> <li>• Project supervision.</li> <li>• Survey during construction.</li> <li>• Safety procedures.</li> <li>• All Personal Protective Equipment.</li> <li>• Transportation</li> <li>• Food supply</li> <li>• Lodging</li> </ul>
<b>QUALITY OR PERFORMANCE CONSTRAINTS</b>	<ul style="list-style-type: none"> <li>• The Contracting Company will be measured against safety, quality, cost and people-based metrics.</li> <li>• Weekly performed progress will be monitored by the Infrastructure Services Department.</li> <li>• The contractor will report to the Infrastructure Services dept.</li> <li>• Any tasks or modifications not specified in the scope of work must receive approval from the infrastructure team before proceeding.</li> <li>• Safety meetings and JHA's are required.</li> </ul>
<b>EQUIPMENT / PERSONNEL CONSTRAINTS</b>	<ul style="list-style-type: none"> <li>• No equipment nor personnel of the contractor should be used for other projects during the construction.</li> <li>• All equipment and personnel must meet the necessary safety and performance requirement.</li> </ul>
<b>REGULATORY CONSTRAINTS</b>	<ul style="list-style-type: none"> <li>• The project must follow safety regulations, including worker protective equipment.</li> <li>• This scope of work forms the basis of the agreement between the client and the contractor. Any changes or deviations from this scope must be documented and mutually agreed upon.</li> </ul>



**ZiJin**

ROSEBEL GOLD MINES N.V.  
罗斯贝尔金矿有限公司

**Figure 1**

